



CASE HISTORY

Well Intervention

SlikPak™ Plus – Slickline/E-line Inflatable Packer

Location:

Onshore Saudi Arabia



Challenge:

Wellhead change out.

Solution:

Run retrievable Bridge Plug as a barrier to allow wellhead change out.

Well Description:

Vertical water injector, 9-5/8" casing, 6.5" ID restriction

Tools Used:

3.53" OD Retrievable Bridge Plug SlikPak™ Plus

Procedure:

- Run and set Bridge Plug on slickline.
- Pressure test Bridge Plug.
- Change out well head.
- Retrieve Bridge Plug

Results:

- Operation successful.

Value Created:

- Well secured, no NPT or HSE issues.
- Reservoir production increased.

